
Pygame Zero Documentation

Release 1.2.1

Daniel Pope

May 16, 2021

Contents

1	Courses	3
1.1	Introduction to Pygame Zero	3
1.2	Migrating from Scratch	7
2	Reference	15
2.1	Event Hooks	15
2.2	Built-in Objects	22
3	User Guide	39
3.1	Installing Pygame Zero	39
3.2	Running Pygame Zero in IDLE and other IDEs	39
3.3	Tutorials and Resources	40
3.4	Other libraries like Pygame Zero	41
3.5	Changelog	42
4	Improving Pygame Zero	45
4.1	Roadmap	45
4.2	Principles of Pygame Zero	46
4.3	Contributing to Pygame Zero	47
	Index	51

Pygame Zero is for creating games without boilerplate.

It is intended for use in education, so that teachers can teach basic programming without needing to explain the Pygame API or write an event loop.

1.1 Introduction to Pygame Zero

1.1.1 Creating a window

First, create an empty file called `intro.py`.

Verify that this runs and creates a blank window by running

```
pgzrun intro.py
```

Everything in Pygame Zero is optional; a blank file is a valid Pygame Zero script!

You can quit the game by clicking on the window's close button or by pressing `Ctrl-Q` (`-Q` on Mac). If the game stops responding for any reason, you may need to terminate it by pressing `Ctrl-C` in your Terminal window.

1.1.2 Drawing a background

Next, let's add a `draw()` function and set window dimensions. Pygame Zero will call this function whenever it needs to paint the screen.

In `intro.py`, add the following:

```
1 WIDTH = 300
2 HEIGHT = 300
3
4 def draw():
5     screen.fill((128, 0, 0))
```

Re-run `pgzrun intro.py` and the screen should now be a reddish square!

What is this code doing?

`WIDTH` and `HEIGHT` control the width and height of your window. The code sets the window size to be 300 pixels in each dimension.

`screen` is a built-in that represents the window display. It has a *range of methods for drawing sprites and shapes*. The `screen.fill()` method call is filling the screen with a solid colour, specified as a (red, green, blue) colour tuple. (128, 0, 0) will be a medium-dark red. Try changing these values with numbers between 0 and 255 and see what colors you can create.

Let's set up a sprite that we can animate.

1.1.3 Draw a sprite

Before we can draw anything, we'll need to save an alien sprite to use. You can right click on this one and save it ("Save Image As..." or similar).



(This sprite has a transparency (or "alpha") channel, which is great for games! But it's designed for a dark background, so you may not be able to see the alien's space helmet until it is shown in the game).

Tip: You can find lots of free sprites, including this one, on kenney.nl. This one comes from the [Platformer Art Deluxe pack](#).

You need to save the file in the right place so that Pygame Zero can find it. Create a directory called `images` and save the image into it as `alien.png`. Both of those must be lower case. Pygame Zero will complain otherwise, to alert you to a potential cross-platform compatibility pitfall.

If you've done that, your project should look like this:

```
.
├── images/
│   └── alien.png
└── intro.py
```

`images/` is the standard directory that Pygame Zero will look in to find your images.

There's a built-in class called `Actor` that you can use to represent a graphic to be drawn to the screen.

Let's define one now. Change the `intro.py` file to read:

```
1 alien = Actor('alien')
2 alien.pos = 100, 56
3
4 WIDTH = 500
5 HEIGHT = alien.height + 20
6
7 def draw():
8     screen.clear()
9     alien.draw()
```

Your alien should now be appearing on screen! By passing the string `'alien'` to the `Actor` class, it automatically loads the sprite, and has attributes like positioning and dimensions. This allows us to set the `HEIGHT` of the window based on the height of the alien.

The `alien.draw()` method draws the sprite to the screen at its current position.

1.1.4 Moving the alien

Let's set the alien off-screen; change the `alien.pos` line to read:

```
alien.topright = 0, 10
```

Note how you can assign to `topright` to move the alien actor by its top-right corner. If the right-hand edge of the alien is at 0, the the alien is just offscreen to the left. Now let's make it move. Add the following code to the bottom of the file:

```
def update():
    alien.left += 2
    if alien.left > WIDTH:
        alien.right = 0
```

Pygame Zero will call your `update()` function once every frame. Moving the alien a small number of pixels every frame will cause it to slide across the screen. Once it slides off the right-hand side of the screen, we reset it back to the left.

1.1.5 Handling clicks

Let's make the game do something when you click on the alien. To do this we need to define a function called `on_mouse_down()`. Add this to the source code:

```
1 def on_mouse_down(pos):
2     if alien.collidepoint(pos):
3         print("Eek!")
4     else:
5         print("You missed me!")
```

You should run the game and try clicking on and off the alien.

Pygame Zero is smart about how it calls your functions. If you don't define your function to take a `pos` parameter, Pygame Zero will call it without a position. There's also a `button` parameter for `on_mouse_down`. So we could have written:

```
def on_mouse_down():
    print("You clicked!")
```

or:

```
def on_mouse_down(pos, button):
    if button == mouse.LEFT and alien.collidepoint(pos):
        print("Eek!")
```

1.1.6 Sounds and images

Now let's make the alien appear hurt. Save these files:

- `alien_hurt.png` - save this as `alien_hurt.png` in the `images` directory.
- `eep.wav` - create a directory called `sounds` and save this as `eep.wav` in that directory.

Your project should now look like this:

```
.
├── images/
│   ├── alien.png
│   └── alien_hurt.png
├── sounds/
│   └── eep.wav
└── intro.py
```

sounds/ is the standard directory that Pygame Zero will look in to find your sound files.

Now let's change the `on_mouse_down` function to use these new resources:

```
def on_mouse_down(pos):
    if alien.collidepoint(pos):
        sounds.eep.play()
        alien.image = 'alien_hurt'
```

Now when you click on the alien, you should hear a sound, and the sprite will change to an unhappy alien.

There's a bug in this game though; the alien doesn't ever change back to a happy alien (but the sound will play on each click). Let's fix this next.

1.1.7 Clock

If you're familiar with Python outside of games programming, you might know the `time.sleep()` method that inserts a delay. You might be tempted to write code like this:

```
1 def on_mouse_down(pos):
2     if alien.collidepoint(pos):
3         sounds.eep.play()
4         alien.image = 'alien_hurt'
5         time.sleep(1)
6         alien.image = 'alien'
```

Unfortunately, this is not at all suitable for use in a game. `time.sleep()` blocks all activity; we want the game to go on running and animating. In fact we need to return from `on_mouse_down`, and let the game work out when to reset the alien as part of its normal processing, all the while running your `draw()` and `update()` methods.

This is not difficult with Pygame Zero, because it has a built-in `Clock` that can schedule functions to be called later.

First, let's "refactor" (ie. re-organise the code). We can create functions to set the alien as hurt and also to change it back to normal:

```
1 def on_mouse_down(pos):
2     if alien.collidepoint(pos):
3         set_alien_hurt()
4
5
6 def set_alien_hurt():
7     alien.image = 'alien_hurt'
8     sounds.eep.play()
9
10
11 def set_alien_normal():
12     alien.image = 'alien'
```

This is not going to do anything different yet. `set_alien_normal()` won't be called. But let's change `set_alien_hurt()` to use the clock, so that the `set_alien_normal()` will be called a little while after.

```
def set_alien_hurt():
    alien.image = 'alien_hurt'
    sounds.eep.play()
    clock.schedule_unique(set_alien_normal, 1.0)
```

`clock.schedule_unique()` will cause `set_alien_normal()` to be called after 1.0 second. `schedule_unique()` also prevents the same function being scheduled more than once, such as if you click very rapidly.

Try it, and you'll see the alien revert to normal after 1 second. Try clicking rapidly and verify that the alien doesn't revert until 1 second after the last click.

1.1.8 Summary

We've seen how to load and draw sprites, play sounds, handle input events, and use the built-in clock.

You might like to expand the game to keep score, or make the alien move more erratically.

There are lots more features built in to make Pygame Zero easy to use. Check out the *[built in objects](#)* to learn how to use the rest of the API.

1.2 Migrating from Scratch

This tutorial will compare an implementation of Flappy Bird written in Scratch with one written in Pygame Zero. The Scratch and Pygame Zero programs are similar to a remarkable extent.

The [Pygame Zero version](#) can be found in Pygame Zero repository.


You can also download the [Scratch version](#) from the repository.

The Pygame Zero version includes scoring logic, which is omitted in the code examples on this page to make it a closer comparison.

The Python code shown below is re-arranged for clarity within the examples.

1.2.1 The stage

Here's how the stage is laid out in our Scratch program:



There are just three objects, aside from the background: the bird, and the top and bottom pipes.

This corresponds to the Pygame Zero code setting these objects up as `Actors`:

```
bird = Actor('bird1', (75, 200))
pipe_top = Actor('top', anchor=('left', 'bottom'))
pipe_bottom = Actor('bottom', anchor=('left', 'top'))
```



In Pygame Zero we also have to ensure we draw these objects. In principle this gives a little more flexibility about how to draw the scene:

```
def draw():
    screen.blit('background', (0, 0))
    pipe_top.draw()
    pipe_bottom.draw()
    bird.draw()
```

1.2.2 Pipe movement

The pipes move at a constant rate irrespective of the bird. When they move off the left-hand side of the screen, they loop around to the right, and their vertical position moves at random.

In Scratch this can be achieved by creating two different scripts for the top and bottom pipe.



To summarise what's happening here:

- The condition `x position < -240` is true when a pipe is off the left-hand side of the screen, and this is the trigger to reset the pipes.

- The `pipe_height` variable is used to coordinate the two pipes. Because the gap between them should remain the same, we can't pick *both* heights randomly. Therefore one of the scripts has this logic and the other doesn't.
- The set `y` position to pipe height ± 230 sets one pipe to be above `pipe_height` and the other pipe below `pipe_height`.

This code becomes much simpler in Pygame Zero. We could write a single function that updates both pipes. In fact I split it a different way to make it clear that the reset actions go together:

```
import random

WIDTH = 400
HEIGHT = 708
GAP = 130
SPEED = 3

def reset_pipes():
    pipe_gap_y = random.randint(200, HEIGHT - 200)
    pipe_top.pos = (WIDTH, pipe_gap_y - GAP // 2)
    pipe_bottom.pos = (WIDTH, pipe_gap_y + GAP // 2)

def update_pipes():
    pipe_top.left -= SPEED
    pipe_bottom.left -= SPEED
    if pipe_top.right < 0:
        reset_pipes()
```

A small difference here is that I can extract values that I want to re-use as “constants”, spelled in UPPERCASE. This lets me change them in one place when I want to tune the game. For example, in the code above, I could widen or narrow the gap between the two pipes simply by changing `GAP`.

The biggest thing that differs is that there is no *forever* loop in Python code. This is the big difference between Scratch and most text-based programming languages: you must update the game by one animation step and then return. Returning gives Pygame Zero a chance to do things like processing input or redrawing the screen. Loop forever and the game would just sit there, so any loops need to finish quickly.

Pygame Zero calls an `update()` function when it wants you to update the animation by one step, so we just need to a call to `update_walls()`:

```
def update():
    update_walls()
```

1.2.3 The Bird

The patterns described above for how Scratch logic translates to Python code also apply for the bird logic. Let's look at the Python code first this time.

The code to update the bird is organised into a function called `update_bird()`. The first thing this function contains is some code to move the bird according to gravity:

```
GRAVITY = 0.3

# Initial state of the bird
bird.dead = False
bird.vy = 0

def update_bird():
```

(continues on next page)

(continued from previous page)

```

uy = bird.vy
bird.vy += GRAVITY
bird.y += bird.vy
bird.x = 75

```

This is a simple gravity formula:

- Gravity means constant **acceleration downwards**.
- Acceleration is change in **velocity**.
- Velocity is change in **position**.

To represent this we need to track a variable `bird.vy`, which is the bird's velocity in the `y` direction. This is a new variable that we are defining, not something that Pygame Zero provides for us.

- Gravity means constant acceleration downwards: `GRAVITY` is greater than 0.
- Acceleration is change in velocity: `GRAVITY` gets added to `bird.vy`
- Velocity is change in position: `bird.vy` gets added to `bird.y`

Note that the bird does not move horizontally! Its `x` position stays at 75 through the whole game. We simulate movement by moving the pipes towards it. This looks as though it's a moving camera following the bird. So there's no need for a `vx` variable in this game.

The next section makes the bird flap its wings:

```

if not bird.dead:
    if bird.vy < -3:
        bird.image = 'bird2'
    else:
        bird.image = 'bird1'

```

This checks if the bird is moving upwards or downwards. We show the `bird2` image if it is moving upwards fast and the `bird1` image otherwise. (-3 was picked by trial and error to make this look convincing).

The next section checks if the bird has collided with a wall:

```

if bird.colliderect(pipe_top) or bird.colliderect(pipe_bottom):
    bird.dead = True
    bird.image = 'birddead'

```

If so we set `bird.dead` to `True`. This is a **boolean value** meaning it is either `True` or `False`. We can use this to easily check if the bird is alive. If it isn't alive it won't respond to player input.

And the final section checks if the bird has fallen off the bottom (or the top) of the game screen. If so it resets the bird:

```

if not 0 < bird.y < 720:
    bird.y = 200
    bird.dead = False
    bird.vy = 0
    reset_pipes()

```

What's `reset_pipes()` doing there? Because I'd organised my pipes code to be a separate function, I can just call it whenever I want to reset my walls. In this case it makes it a better game because it gives the player a chance to react when the bird moves back to its start position.

Again, this needs to be called every frame, so we add it to `update()`:

```
def update():
    update_walls()
    update_bird()
```


The final part of the bird logic is that it has to respond to player control. When we press a key, the bird flaps upwards. Pygame Zero will call an `on_key_down()` function - if you've defined one - whenever a key is pressed:

```
FLAP_VELOCITY = -6.5

def on_key_down():
    if not bird.dead:
        bird.vy = FLAP_VELOCITY
```

Here, if the bird is not dead, we set its `vy` to a negative number: in Pygame Zero this means it starts moving upwards. You should be able to find a lot of parallels between the Python code and this Scratch code:





The biggest differences between Scratch and Pygame Zero are these:

- You cannot loop forever in Pygame Zero - just update for one frame and then return.
- The coordinates are different. In Pygame Zero, the top left of the screen is $x = 0$, $y = 0$. The x direction goes from left to right as before, but y goes down the screen! This is why `GRAVITY` is a positive number and `FLAP_VELOCITY` is a negative number in Python.
- `bird.dead` is a bool, so I can write code like `if not bird.dead` instead of `dead = 0` as in Scratch.

1.2.4 Summary

Many of the concepts available in Scratch can be translated directly into Pygame Zero.

Here are some comparisons:

In Scratch	In Pygame Zero
change y by 1 (up)	<code>bird.y -= 1</code>
change y by -1 (down)	<code>bird.y += 1</code>
set costume to <name>	<code>bird.image = 'name'</code>
if <code>dead = 0</code>	<code>if not bird.dead:</code>
set <code>dead</code> to 0	<code>bird.dead = False</code>
if touching Top?	<code>if bird.colliderect(pipe_top)</code>
When Flag clicked... forever	Put code into the <code>update()</code> function.
When [any] key pressed	<code>def on_key_down():</code>
pick random a to b	<code>import random to load the random module, then random.randint(a, b)</code>
(0, 0) is the centre of the stage	(0, 0) is the top-left of the window

In some cases, the code is simpler in Python because it can be organised in a way that helps it make sense when you read it.

The power of Pygame Zero's actors also makes the coordinate manipulation easier. We used the `anchor` position to position the pipes, and we were able to see if a pipe was off-screen by checking `pipe_top.right < 0` rather than `if x position < -240`.

2.1 Event Hooks

Pygame Zero will automatically pick up and call event hooks that you define. This approach saves you from having to implement the event loop machinery yourself.

2.1.1 Game Loop Hooks

A typical game loop looks a bit like this:

```
while game_has_not_ended():
    process_input()
    update()
    draw()
```

Input processing is a bit more complicated, but Pygame Zero allows you to easily define the `update()` and `draw()` functions within your game module.

draw()

Called by Pygame Zero when it needs to redraw your game window.

`draw()` must take no arguments.

Pygame Zero attempts to work out when the game screen needs to be redrawn to avoid redrawing if nothing has changed. On each step of the game loop it will draw the screen in the following situations:

- If you have defined an `update()` function (see below).
- If a clock event fires.
- If an input event has been triggered.

One way this can catch you out is if you attempt to modify or animate something within the draw function. For example, this code is wrong: the alien is not guaranteed to continue moving across the screen:

```
def draw():
    alien.left += 1
    alien.draw()
```

The correct code uses `update()` to modify or animate things and `draw` simply to paint the screen:

```
def draw():
    alien.draw()

def update():
    alien.left += 1
```

update() or *update(dt)*

Called by Pygame Zero to step your game logic. This will be called repeatedly, 60 times a second.

There are two different approaches to writing an update function.

In simple games you can assume a small time step (a fraction of a second) has elapsed between each call to `update()`. Perhaps you don't even care how big that time step is: you can just move objects by a fixed number of pixels per frame (or accelerate them by a fixed constant, etc.)

A more advanced approach is to base your movement and physics calculations on the actual amount of time that has elapsed between calls. This can give smoother animation, but the calculations involved can be harder and you must take more care to avoid unpredictable behaviour when the time steps grow larger.

To use a time-based approach, you can change the update function to take a single parameter. If your update function takes an argument, Pygame Zero will pass it the elapsed time in seconds. You can use this to scale your movement calculations.

2.1.2 Event Handling Hooks

Similar to the game loop hooks, your Pygame Zero program can respond to input events by defining functions with specific names.

Somewhat like in the case of `update()`, Pygame Zero will inspect your event handler functions to determine how to call them. So you don't need to make your handler functions take arguments. For example, Pygame Zero will be happy to call any of these variations of an `on_mouse_down` function:

```
def on_mouse_down():
    print("Mouse button clicked")

def on_mouse_down(pos):
    print("Mouse button clicked at", pos)

def on_mouse_down(button):
    print("Mouse button", button, "clicked")

def on_mouse_down(pos, button):
    print("Mouse button", button, "clicked at", pos)
```

It does this by looking at the names of the parameters, so they must be spelled exactly as above. Each event hook has a different set of parameters that you can use, as described below.

on_mouse_down (*[pos]* [*, button*])

Called when a mouse button is depressed.

Parameters

- **pos** – A tuple (x, y) that gives the location of the mouse pointer when the button was pressed.
- **button** – A *mouse* enum value indicating the button that was pressed.

on_mouse_up ([*pos*][, *button*])

Called when a mouse button is released.

Parameters

- **pos** – A tuple (x, y) that gives the location of the mouse pointer when the button was released.
- **button** – A *mouse* enum value indicating the button that was released.

on_mouse_move ([*pos*][, *rel*][, *buttons*])

Called when the mouse is moved.

Parameters

- **pos** – A tuple (x, y) that gives the location that the mouse pointer moved to.
- **rel** – A tuple (delta_x, delta_y) that represent the change in the mouse pointer's position.
- **buttons** – A set of *mouse* enum values indicating the buttons that were depressed during the move.

To handle mouse drags, use code such as the following:

```
def on_mouse_move(rel, buttons):
    if mouse.LEFT in buttons:
        # the mouse was dragged, do something with `rel`
        ...
```

on_key_down ([*key*][, *mod*][, *unicode*])

Called when a key is depressed.

Parameters

- **key** – An integer indicating the key that was pressed (see *below*).
- **unicode** – Where relevant, the character that was typed. Not all keys will result in printable characters - many may be control characters. In the event that a key doesn't correspond to a Unicode character, this will be the empty string.
- **mod** – A bitmask of modifier keys that were depressed.

on_key_up ([*key*][, *mod*])

Called when a key is released.

Parameters

- **key** – An integer indicating the key that was released (see *below*).
- **mod** – A bitmask of modifier keys that were depressed.

on_music_end()

Called when a *music track* finishes.

Note that this will not be called if the track is configured to loop.

Buttons and Keys

Built-in objects `mouse` and `keys` can be used to determine which buttons or keys were pressed in the above events.

Note that mouse scrollwheel events appear as button presses with the below `WHEEL_UP`/`WHEEL_DOWN` button constants.

class `mouse`

A built-in enumeration of buttons that can be received by the `on_mouse_*` handlers.

LEFT
MIDDLE
RIGHT
WHEEL_UP
WHEEL_DOWN

class `keys`

A built-in enumeration of keys that can be received by the `on_key_*` handlers.

BACKSPACE
TAB
CLEAR
RETURN
PAUSE
ESCAPE
SPACE
EXCLAIM
QUOTEDBL
HASH
DOLLAR
AMPERSAND
QUOTE
LEFTPAREN
RIGHTPAREN
ASTERISK
PLUS
COMMA
MINUS
PERIOD
SLASH
K_0
K_1
K_2

K_3

K_4

K_5

K_6

K_7

K_8

K_9

COLON

SEMICOLON

LESS

EQUALS

GREATER

QUESTION

AT

LEFTBRACKET

BACKSLASH

RIGHTBRACKET

CARET

UNDERSCORE

BACKQUOTE

A

B

C

D

E

F

G

H

I

J

K

L

M

N

O

P

Q

R

S

T

U

V

W

X

Y

Z

DELETE

KP0

KP1

KP2

KP3

KP4

KP5

KP6

KP7

KP8

KP9

KP_PERIOD

KP_DIVIDE

KP_MULTIPLY

KP_MINUS

KP_PLUS

KP_ENTER

KP_EQUALS

UP

DOWN

RIGHT

LEFT

INSERT

HOME

END

PAGEUP

PAGEDOWN

F1

F2

F3

F4

F5

F6

F7

F8

F9

F10

F11

F12

F13

F14

F15

NUMLOCK

CAPSLOCK

SCROLLLOCK

RSHIFT

LSHIFT

RCTRL

LCTRL

RALT

LALT

RMETA

LMETA

LSUPER

RSUPER

MODE

HELP

PRINT

SYSREQ

BREAK

MENU

POWER

EURO

LAST

Additionally you can access a set of constants that represent modifier keys:

class keymods

Constants representing modifier keys that may have been depressed during an `on_key_up/on_key_down` event.

LSHIFT

RSHIFT

SHIFT

LCTRL

RCTRL

CTRL

LALT

RALT

ALT

LMETA

RMETA

META

NUM

CAPS

MODE

2.2 Built-in Objects

Pygame Zero provides useful built-in objects to help you make games easily.

2.2.1 Screen

Text Formatting

The *Screen*'s `draw.text()` method has a very rich set of methods for position and formatting of text. Some examples:

```
screen.draw.text("Text color", (50, 30), color="orange")
screen.draw.text("Font name and size", (20, 100), fontname="Boogaloo", fontsize=60)
screen.draw.text("Positioned text", topright=(840, 20))
screen.draw.text("Allow me to demonstrate wrapped text.", (90, 210), width=180, ↵
↪lineheight=1.5)
screen.draw.text("Outlined text", (400, 70), owidth=1.5, ocolor=(255,255,0), color=(0, ↵
↪0,0))
screen.draw.text("Drop shadow", (640, 110), shadow=(2,2), scolor="#202020")
screen.draw.text("Color gradient", (540, 170), color="red", gcolor="purple")
```

(continues on next page)

(continued from previous page)

```
screen.draw.text("Transparency", (700, 240), alpha=0.1)
screen.draw.text("Vertical text", midleft=(40, 440), angle=90)
screen.draw.text("All together now:\nCombining the above options",
    midbottom=(427, 460), width=360, fontname="Boogaloo", fontsize=48,
    color="#AAFF00", gcolor="#66AA00", owidth=1.5, ocolor="black", alpha=0.8)
```

In its simplest usage, `screen.draw.text` requires the string you want to draw, and the position. You can either do this by passing coordinates as the second argument (which is the top left of where the text will appear), or use the positioning keyword arguments (described later):

```
screen.draw.text("hello world", (20, 100))
```

`screen.draw.text` takes many optional keyword arguments, described below.

Font name and size

Fonts are loaded from a directory named `fonts`, in a similar way to the handling of images and sounds. Fonts must be in `.ttf` format. For example:

```
screen.draw.text("hello world", (100, 100), fontname="Viga", fontsize=32)
```

Keyword arguments:

- `fontname`: filename of the font to draw. By default, use the system font.
- `fontsize`: size of the font to use, in pixels. Defaults to 24.
- `antialias`: whether to render with antialiasing. Defaults to `True`.

Color and background color

```
screen.draw.text("hello world", (100, 100), color=(200, 200, 200), background="gray")
```

Keyword arguments:

- `color`: foreground color to use. Defaults to white.
- `background`: background color to use. Defaults to `None`.

`color` (as well as `background`, `ocolor`, `scolor`, and `gcolor`) can be an (r, g, b) sequence such as (255, 127, 0), a `pygame.Color` object, a color name such as "orange", an HTML hex color string such as "#FF7F00", or a string representing a hex color number such as "0xFF7F00".

`background` can also be `None`, in which case the background is transparent. Unlike `pygame.font.Font.render`, it's generally not more efficient to set a background color when calling `screen.draw.text`. So only specify a background color if you actually want one.

Colors with alpha transparency are not supported (except for the special case of invisible text with outlines or drop shadows - see below). See the `alpha` keyword argument for transparency.

Positioning

```
screen.draw.text("hello world", centery=50, right=300)
screen.draw.text("hello world", midtop=(400, 0))
```

Keyword arguments:

```
top left bottom right
topleft bottomleft topright bottomright
midtop midleft midbottom midright
center centerx centery
```

Positioning keyword arguments behave like the corresponding properties of `pygame.Rect`. Either specify two arguments, corresponding to the horizontal and vertical positions of the box, or a single argument that specifies both.

If the position is overspecified (e.g. both `left` and `right` are given), then extra specifications will be (arbitrarily but deterministically) discarded. For constrained text, see the section on `screen.draw.textbox` below.

Word wrap

```
screen.draw.text("splitting\nlines", (100, 100))
screen.draw.text("splitting lines", (100, 100), width=60)
```

Keyword arguments:

- `width`: maximum width of the text to draw, in pixels. Defaults to `None`.
- `widthem`: maximum width of the text to draw, in font-based em units. Defaults to `None`.
- `lineheight`: vertical spacing between lines, in units of the font's default line height. Defaults to `1.0`.

`screen.draw.text` will always wrap lines at newline (`\n`) characters. If `width` or `widthem` is set, it will also try to wrap lines in order to keep each line shorter than the given width. The text is not guaranteed to be within the given width, because wrapping only occurs at space characters, so if a single word is too long to fit on a line, it will not be broken up. Outline and drop shadow are also not accounted for, so they may extend beyond the given width.

You can prevent wrapping on a particular space with non-breaking space characters (`\u00A0`).

Text alignment

```
screen.draw.text("hello\nworld", bottomright=(500, 400), align="left")
```

Keyword argument:

- `align`: horizontal positioning of lines with respect to each other. Defaults to `None`.

`align` determines how lines are positioned horizontally with respect to each other, when more than one line is drawn. Valid values for `align` are the strings `"left"`, `"center"`, or `"right"`, a numerical value between `0.0` (for left alignment) and `1.0` (for right alignment), or `None`.

If `align` is `None`, the alignment is determined based on other arguments, in a way that should be what you want most of the time. It depends on any positioning arguments (`topleft`, `centerx`, etc.), `anchor`, and finally defaults to `"left"`. I suggest you generally trust the default alignment, and only specify `align` if something doesn't look right.

Outline

```
screen.draw.text("hello world", (100, 100), owidth=1, ocolor="blue")
```

Keyword arguments:

- `owidth`: outline thickness, in outline units. Defaults to `None`.
- `ocolor`: outline color. Defaults to `"black"`.

The text will be outlined if `owidth` is specified. The outlining is a crude manual method, and will probably look bad at large sizes. The units of `owidth` are chosen so that `1.0` is a good typical value for outlines. Specifically, they're the font size divided by 24.

As a special case, setting `color` to a transparent value (e.g. `(0, 0, 0, 0)`) while using outlines will cause the text to be invisible, giving a hollow outline. (This feature is not compatible with `gcolor`.)

Valid values for `ocolor` are the same as for `color`.

Drop shadow

```
screen.draw.text("hello world", (100, 100), shadow=(1.0,1.0), scolor="blue")
```

Keyword arguments:

- `shadow`: (x,y) values representing the drop shadow offset, in shadow units. Defaults to `None`.
- `scolor`: drop shadow color. Defaults to `"black"`.

The text will have a drop shadow if `shadow` is specified. It must be set to a 2-element sequence representing the x and y offsets of the drop shadow, which can be positive, negative, or 0. For example, `shadow=(1.0, 1.0)` corresponds to a shadow down and to the right of the text. `shadow=(0, -1.2)` corresponds to a shadow higher than the text.

The units of `shadow` are chosen so that `1.0` is a good typical value for the offset. Specifically, they're the font size divided by 18.

As a special case, setting `color` to a transparent value (e.g. `(0, 0, 0, 0)`) while using drop shadow will cause the text to be invisible, giving a hollow shadow. (This feature is not compatible with `gcolor`.)

Valid values for `scolor` are the same as for `color`.

Gradient color

```
screen.draw.text("hello world", (100, 100), color="black", gcolor="green")
```

Keyword argument:

- `gcolor`: Lower gradient stop color. Defaults to `None`.

Specify `gcolor` to color the text with a vertical color gradient. The text's color will be `color` at the top and `gcolor` at the bottom. Positioning of the gradient stops and orientation of the gradient are hard coded and cannot be specified.

Requires `pygame.surfarray` module, which uses `numpy` or `Numeric` library.

Alpha transparency

```
screen.draw.text("hello world", (100, 100), alpha=0.5)
```

Keyword argument:

- `alpha`: alpha transparency value, between 0 and 1. Defaults to `1.0`.

In order to maximize reuse of cached transparent surfaces, the value of `alpha` is rounded.

Requires `pygame.surfarray` module, which uses `numpy` or `Numeric` library.

Anchored positioning

```
screen.draw.text("hello world", (100, 100), anchor=(0.3, 0.7))
```

Keyword argument:

- **anchor**: a length-2 sequence of horizontal and vertical anchor fractions. Defaults to (0.0, 0.0).

anchor specifies how the text is anchored to the given position, when no positioning keyword arguments are passed. The two values in **anchor** can take arbitrary values between 0.0 and 1.0. An **anchor** value of (0, 0), the default, means that the given position is the top left of the text. A value of (1, 1) means the given position is the bottom right of the text.

Rotation

```
screen.draw.text("hello world", (100, 100), angle=10)
```

Keyword argument:

- **angle**: counterclockwise rotation angle in degrees. Defaults to 0.

Positioning of rotated surfaces is tricky. When drawing rotated text, the anchor point, the position you actually specify, remains fixed, and the text rotates around it. For instance, if you specify the top left of the text to be at (100, 100) with an angle of 90, then the Surface will actually be drawn so that its bottom left is at (100, 100).

If you find that confusing, try specifying the center. If you anchor the text at the center, then the center will remain fixed, no matter how you rotate it.

In order to maximize reuse of cached rotated surfaces, the value of **angle** is rounded to the nearest multiple of 3 degrees.

Constrained text

```
screen.draw.textbox("hello world", (100, 100, 200, 50))
```

`screen.draw.textbox` requires two arguments: the text to be drawn, and a `pygame.Rect` or a Rect-like object to stay within. The font size will be chosen to be as large as possible while staying within the box. Other than **fontsize** and positional arguments, you can pass all the same keyword arguments to `screen.draw.textbox` as to `screen.draw.text`.

The `screen` object represents your game screen.

It is a thin wrapper around a Pygame surface that allows you to easily draw images to the screen (“blit” them).

class Screen

surface

The raw [Pygame surface](#) that represents the screen buffer. You can use this for advanced graphics operations.

clear()

Reset the screen to black.

fill((red, green, blue))

Fill the screen with a solid color.

blit (*image*, (*left*, *top*))

Draw the image to the screen at the given position.

`blit()` accepts either a `Surface` or a string as its `image` parameter. If `image` is a `str` then the named image will be loaded from the `images/` directory.

`draw.line` (*start*, *end*, (*r*, *g*, *b*))

Draw a line from start to end.

`draw.circle` (*pos*, *radius*, (*r*, *g*, *b*))

Draw the outline of a circle.

`draw.filled_circle` (*pos*, *radius*, (*r*, *g*, *b*))

Draw a filled circle.

`draw.rect` (*rect*, (*r*, *g*, *b*))

Draw the outline of a rectangle.

Takes a [Rect](#).

`draw.filled_rect` (*rect*, (*r*, *g*, *b*))

Draw a filled rectangle.

`draw.text` (*text*[, *pos*], ***kwargs*)

Draw text.

There's an extremely rich API for positioning and formatting text; see [Text Formatting](#) for full details.

`draw.textbox` (*text*, *rect*, ***kwargs*)

Draw text, sized to fill the given [Rect](#).

There's an extremely rich API for formatting text; see [Text Formatting](#) for full details.

2.2.2 Rect

The [Pygame Rect](#) class is available as a built in. This can be used in a variety of ways, from detecting clicks within a region to drawing a box onto the screen:

For example, you can draw a box with:

```
RED = 200, 0, 0
BOX = Rect((20, 20), (100, 100))

def draw():
    screen.draw.rect(BOX, RED)
```

2.2.3 Resource Loading

The `images` and `sounds` objects can be used to load images and sounds from files stored in the `images` and `sounds` subdirectories respectively. Pygame Zero will handle loading of these resources on demand and will cache them to avoid reloading them.

You generally need to ensure that your images are named with lowercase letters, numbers and underscores only. They also have to start with a letter.

File names like these will work well with the resource loader:

```
alien.png
alien_hurt.png
alien_run_7.png
```

These will not work:

```
3.png
3degrees.png
my-cat.png
sam's dog.png
```

Images

Pygame Zero can load images in .png, .gif, and .jpg formats. PNG is recommended: it will allow high quality images with transparency.

We need to ensure an images directory is set up. If your project contains the following files:

```
space_game.py
images/alien.png
```

Then `space_game.py` could draw the ‘alien’ sprite to the screen with this code:

```
def draw():
    screen.clear()
    screen.blit('alien', (10, 10))
```

The name passed to `blit()` is the name of the image file within the images directory, without the file extension.

Or using the *Actors* API,

```
alien = Actor('alien')

def draw():
    alien.draw()
```

There are some restrictions on the file names in both cases: they may only contain lowercase latin letters, numbers and underscores. This is to prevent compatibility problems when your game is played on a different operating system that has different case sensitivity.

Image Surfaces

You can also load images from the `images` directory using the `images` object. This allows you to work with the image data itself, query its dimensions and so on:

```
forest = []
for i in range(5):
    forest.append(
        Actor('tree', topleft=(images.tree.width * i, 0))
    )
```

Each loaded image is a Pygame Surface. You will typically use `screen.blit(...)` to draw this to the screen. It also provides handy methods to query the size of the image in pixels:

class Surface

get_width()

Returns the width of the image in pixels.

get_height()

Returns the height of the image in pixels.

get_size()

Returns a tuple (width, height) indicating the size in pixels of the surface.

get_rect()Get a `Rect` that is pre-populated with the bounds of the image if the image was located at the origin.

Effectively this is equivalent to:

```
Rect((0, 0), image.get_size())
```

Sounds

Pygame Zero can load sounds in `.wav` and `.ogg` formats. WAV is great for small sound effects, while OGG is a compressed format that is more suited to music. You can find free `.ogg` and `.wav` files online that can be used in your game.

We need to ensure a sounds directory is set up. If your project contains the following files:

```
drum_kit.py
sounds/drum.wav
```

Then `drum_kit.py` could play the drum sound whenever the mouse is clicked with this code:

```
def on_mouse_down():
    sounds.drum.play()
```

Each loaded sound is a Pygame `Sound`, and has various methods to play and stop the sound as well as query its length in seconds:

class Sound

play()

Play the sound.

play(loops)

Play the sound, but loop it a number of times.

Parameters loops – The number of times to loop. If you pass `-1` as the number of times to loop, the sound will loop forever (or until you call `Sound.stop()`)

stop()

Stop playing the sound.

get_length()

Get the duration of the sound in seconds.

You should avoid using the `sounds` object to play longer pieces of music. Because the sounds system will fully load the music into memory before playing it, this can use a lot of memory, as well as introducing a delay while the music is loaded.

2.2.4 Music

New in version 1.1.

Warning: The music API is experimental and may be subject to cross-platform portability issues.

In particular:

- MP3 may not be available on some Linux distributions.
- Some OGG Vorbis files seem to hang Pygame with 100% CPU.

In the case of the latter issue, the problem may be fixed by re-encoding (possibly with a different encoder).

A built-in object called `music` provides access to play music from within a `music/` directory (alongside your `images/` and `sounds/` directories, if you have them). The music system will load the track a little bit at a time while the music plays, avoiding the problems with using `sounds` to play longer tracks.

Another difference to the `sounds` system is that only one music track can be playing at a time. If you play a different track, the previously playing track will be stopped.

`music.play(name)`

Play a music track from the given file. The track will loop indefinitely.

This replaces the currently playing track and cancels any tracks previously queued with `queue()`.

You do not need to include the extension in the track name; for example, to play the file `handel.mp3` on a loop:

```
music.play('handel')
```

`music.play_once(name)`

Similar to `play()`, but the music will stop after playing through once.

`music.queue(name)`

Similar to `play_once()`, but instead of stopping the current music, the track will be queued to play after the current track finishes (or after any other previously queued tracks).

`music.stop()`

Stop the music.

`music.pause()`

Pause the music temporarily. It can be resumed by calling `unpause()`.

`music.unpause()`

Unpause the music.

`music.is_playing()`

Returns True if the music is playing (and is not paused), False otherwise.

`music.fadeout(duration)`

Fade out and eventually stop the current music playback.

Parameters `duration` – The duration in seconds over which the sound will be faded out. For example, to fade out over half a second, call `music.fadeout(0.5)`.

`music.set_volume(volume)`

Set the volume of the music system.

This takes a number between 0 (meaning silent) and 1 (meaning full volume).

```
music.get_volume()
```

Get the current volume of the music system.

If you have started a music track playing using `music.play_once()`, you can use the `on_music_end()` hook to do something when the music ends - for example, to pick another track at random.

2.2.5 Clock

Often when writing a game, you will want to schedule some game event to occur at a later time. For example, we may want a big boss alien to appear after 60 seconds. Or perhaps a power-up will appear every 20 seconds.

More subtle are the situations when you want to delay some action for a shorter period. For example you might have a laser weapon that takes 1 second to charge up.

We can use the `clock` object to schedule a function to happen in the future.

Let's start by defining a function `fire_laser` that we want to run in the future:

```
def fire_laser():
    lasers.append(player.pos)
```

Then when the fire button is pressed, we will ask the `clock` to call it for us after exactly 1 second:

```
def on_mouse_down():
    clock.schedule(fire_laser, 1.0)
```

Note that `fire_laser` is the function itself; without parentheses, it is not being called here! The clock will call it for us.

(It is a good habit to write out times in seconds with a decimal point, like `1.0`. This makes it more obvious when you are reading it back, that you are referring to a time value and not a count of things.)

`clock` provides the following useful methods:

class Clock

schedule (*callback*, *delay*)

Schedule *callback* to be called after the given delay.

Repeated calls will schedule the callback repeatedly.

Parameters

- **callback** – A callable that takes no arguments.
- **delay** – The delay, in seconds, before the function should be called.

schedule_unique (*callback*, *delay*)

Schedule *callback* to be called once after the given delay.

If *callback* was already scheduled, cancel and reschedule it. This applies also if it was scheduled multiple times: after calling `schedule_unique`, it will be scheduled exactly once.

Parameters

- **callback** – A callable that takes no arguments.
- **delay** – The delay, in seconds, before the function should be called.

schedule_interval (*callback*, *interval*)

Schedule *callback* to be called repeatedly.

Parameters

- **callback** – A callable that takes no arguments.
- **interval** – The interval in seconds between calls to *callback*.

unschedule (*callback*)

Unschedule callback if it has been previously scheduled (either because it has been scheduled with `schedule()` and has not yet been called, or because it has been scheduled to repeat with `schedule_interval()`).

Note that the Pygame Zero clock only holds weak references to each callback you give it. It will not fire scheduled events if the objects and methods are not referenced elsewhere. This can help prevent the clock keeping objects alive and continuing to fire unexpectedly after they are otherwise dead.

The downside to the weak references is that you won't be able to schedule lambdas or any other object that has been created purely to be scheduled. You will have to keep a reference to the object.

2.2.6 Actors

Once you have many images moving around in a game it can be convenient to have something that holds in one place the image and where it is on screen. We'll call each moving image on screen an **Actor**. You can create an actor by supplying at least an image name (from the images folder above). To draw the alien talked about above:

```
alien = Actor('alien', (50, 50))

def draw():
    screen.clear()
    alien.draw()
```

You can move the actor around by setting its `pos` attribute in an update:

```
def update():
    if keyboard.left:
        alien.x -= 1
    elif keyboard.right:
        alien.x += 1
```

And you may change the image used to draw the actor by setting its image attribute to some new image name:

```
alien.image = 'alien_hurt'
```

Actors have all the same attributes and methods as *Rect*, including methods like `.colliderect()` which can be used to test whether two actors have collided.


Positioning Actors

If you assign a new value to one of the position attributes then the actor will be moved. For example:

```
alien.right = WIDTH
```

will position the alien so its right-hand side is set to `WIDTH`.

Similarly, you can also set the initial position of the actor in the constructor, by passing one of these as a keyword argument: `pos`, `opleft`, `oprigh`, `obopleft`, `oboprigh`, `midtop`, `midleft`, `midright`, `midbottom` or `center`:




This can be done during creation or by assigning a pair of x, y co-ordinates. For example:


```
WIDTH = 200
HEIGHT = 200

alien = Actor('alien', center=(100,100))

def draw():
    screen.clear()
    alien.draw()
```



Changing `center=(100, 100)` to `midbottom=(100, 200)` gives you:



If you don't specify an initial position, the actor will initially be positioned in the top-left corner (equivalent to `opleft=(0, 0)`).

Anchor point

Actors have an “anchor position”, which is a convenient way to position the actor in the scene. By default, the anchor position is the center, so the `.pos` attribute refers to the center of the actor (and so do the `x` and `y` coordinates). It's common to want to set the anchor point to another part of the sprite (perhaps the feet - so that you can easily set the Actor to be “standing on” something):

```
alien = Actor('alien', anchor=('center', 'bottom'))
spaceship = Actor('spaceship', anchor=(10, 50))
```

`anchor` is specified as a tuple (`xanchor`, `yanchor`), where the values can be floats or the strings `left`, `center/middle`, `right`, `top` or `bottom` as appropriate.

Rotation

New in version 1.2.

The `.angle` attribute of an Actor controls the rotation of the sprite, in degrees, anticlockwise (counterclockwise).

The centre of rotation is the Actor's *anchor point*.

Note that this will change the width and height of the Actor.

For example, to make an asteroid sprite spinning slowly anticlockwise in space:

```
asteroid = Actor('asteroid', center=(300, 300))

def update():
    asteroid.angle += 1
```

To have it spin clockwise, we'd change `update()` to:

```
def update():
    asteroid.angle -= 1
```

As a different example, we could make an actor `ship` always face the mouse pointer. Because `angle_to()` returns 0 for “right”, the sprite we use for “ship” should face right:

```
ship = Actor('ship')

def on_mouse_move(pos):
    ship.angle = ship.angle_to(pos)
```

Remember that angles loop round, so 0 degrees == 360 degrees == 720 degrees. Likewise -180 degrees == 180 degrees.

Distance and angle to

Actors have convenient methods for calculating their distance or angle to other Actors or (x, y) coordinate pairs.

`Actor.distance_to(target)`

Return the distance from this actor's position to target, in pixels.

`Actor.angle_to(target)`

Return the angle from this actor's position to target, in degrees.

This will return a number between -180 and 180 degrees. Right is 0 degrees and the angles increase going anticlockwise.

Therefore:

- Left is 180 degrees.
- Up is 90 degrees.
- Down is -90 degrees.

2.2.7 The Keyboard

You probably noticed that we used the `keyboard` in the above code. If you'd like to know what keys are pressed on the keyboard, you can query the attributes of the `keyboard` builtin. If, say, the left arrow is held down, then `keyboard.left` will be `True`, otherwise it will be `False`.

There are attributes for every key; some examples:

```
keyboard.a # The 'A' key
keyboard.left # The left arrow key
keyboard.rshift # The right shift key
keyboard.kp0 # The '0' key on the keypad
keyboard.k_0 # The main '0' key
```

The full set of key constants is given in the [Buttons and Keys](#) documentation, but the attributes are lowercase, because these are variables not constants.

Deprecated since version 1.1: Uppercase and prefixed attribute names (eg. `keyboard.LEFT` or `keyboard.K_a`) are now deprecated; use lowercase attribute names instead.

New in version 1.1: You can now also query the state of the keys using the `keyboard` constants themselves:

```
keyboard[keys.A] # True if the 'A' key is pressed
keyboard[keys.SPACE] # True if the space bar is pressed
```

2.2.8 Animations

You can animate most things in pygame using the builtin `animate()`. For example, to move an *Actor* from its current position on the screen to the position `(100, 100)`:

```
animate(alien, pos=(100, 100))
```

animate (*object*, *tween*='linear', *duration*=1, *on_finished*=None, ***targets*)

Animate the attributes on object from their current value to that specified in the targets keywords.

Parameters

- **tween** – The type of *tweening* to use.
- **duration** – The duration of the animation, in seconds.
- **on_finished** – Function called when the animation finishes.
- **targets** – The target values for the attributes to animate.

The tween argument can be one of the following:

'linear'	Animate at a constant speed from start to finish
'accelerate'	Start slower and accelerate to finish
'decelerate'	Start fast and decelerate to finish
'accel_decel'	Accelerate to mid point and decelerate to finish
'end_elastic'	Give a little wobble at the end
'start_elastic'	Have a little wobble at the start
'both_elastic'	Have a wobble at both ends
'bounce_end'	Accelerate to the finish and bounce there
'bounce_start'	Bounce at the start
'bounce_start_end'	Bounce at both ends

The `animate()` function returns an `Animation` instance:

class Animation

stop (*complete*=False)

Stop the animation, optionally completing the transition to the final property values.

Parameters **complete** – Set the animated attribute to the target value.

running

This will be True if the animation is running. It will be False when the duration has run or the `stop()` method was called before then.

on_finished

You may set this attribute to a function which will be called when the animation duration runs out. The `on_finished` argument to `animate()` also sets this attribute. It is not called when `stop()` is called. This function takes no arguments.

2.2.9 Tone Generator

New in version 1.2.

Pygame Zero can play tones using a built-in synthesizer.

`tone.play(pitch, duration)`

Play a note at the given pitch for the given duration.

Duration is in seconds.

The *pitch* can be specified as a number in which case it is the frequency of the note in hertz.

Alternatively, the pitch can be specified as a string representing a note name and octave. For example:

- 'E4' would be E in octave 4.
- 'A#5' would be A-sharp in octave 5.
- 'Bb3' would be B-flat in octave 3.

Creating notes, particularly long notes, takes time - up to several milliseconds. You can create your notes ahead of time so that this doesn't slow your game down while it is running:

`tone.create(pitch, duration)`

Create and return a Sound object.

The arguments are as for `play()`, above.

This could be used in a Pygame Zero program like this:

```
beep = tone.create('A3', 0.5)

def on_mouse_down():
    beep.play()
```


3.1 Installing Pygame Zero

3.1.1 On desktop systems

```
pip install pgzero
```

This will also install Pygame. Pre-compiled Pygame packages are available to pip for Windows & Linux (32-bit and 64-bit), and for Mac OS (64-bit only). If you have a different system, you'll need to find a way to install pygame first.

3.1.2 On Raspberry Pi

pgzero has been installed by default since the release of Raspbian Jessie in September 2015!

3.2 Running Pygame Zero in IDLE and other IDEs

New in version 1.2.

Pygame Zero is usually run using a command such as:

```
pgzrun my_program.py
```

Certain programs, such as integrated development environments like IDLE and Edublocks, will only run `python`, not `pgzrun`.

Pygame Zero includes a way of writing a full Python program that can be run using `python`. To do it, put

```
import pgzrun
```

as the very first line of the Pygame Zero program, and put

```
pgzrun.go()
```

as the very last line.

3.2.1 Example

Here is a Pygame Zero program that draws a circle. You can run this by pasting it into IDLE:

```
import pgzrun

WIDTH = 800
HEIGHT = 600

def draw():
    screen.clear()
    screen.draw.circle((400, 300), 30, 'white')

pgzrun.go()
```

3.3 Tutorials and Resources

Here are some tutorials and learning resources which use Pygame Zero.

3.3.1 Books

- [Coding Games in Python](#) (DK) - teaches programming in Python from scratch with Pygame Zero and bright, colourful illustrations.
- [Code the Classics](#) (Raspberry Pi Press) - covers the history of classic computer games and explains how to make them with Pygame Zero.
- [Mission Python](#) (No Starch Press) - takes you through the process of writing one larger game with Pygame Zero.

3.3.2 Online Tutorials

- [Simple Game Tutorials](#) is a collection of step-by-step tutorials which guide you through the process of making some simple games.
- [Coding Games with Pygame Zero and Python](#) - teaches programming in Python for complete beginners, moving into several complete examples.

3.3.3 Magazines

- [MagPi](#), the Raspberry Pi magazine, has covered Pygame Zero several times. MagPi is available in print but is also free to download online.
- [Wireframe](#), also from Raspberry Pi, and also free to download online, is a magazine focused on games, game development, and the game industry, and most issues contain Pygame Zero examples.

3.3.4 Video Tutorials

There are numerous Pygame Zero tutorial videos on [YouTube](#); here are some:

- [A brief introduction to Pygame Zero](#) (Neil Muller)
- [How to use Pygame Zero](#) (TeCoEd)

3.4 Other libraries like Pygame Zero

Pygame Zero started a trend for Python “zero” libraries. Our friends have created these great libraries. Some of these can be combined with Pygame Zero!

3.4.1 Network Zero

[Network Zero](#) makes it simpler to have several machines or several processes on one machine discovering each other and talking across a network.

Caution: If you want to use Network Zero with Pygame Zero, make sure you don’t let it **block** (stop everything while waiting for messages). This will interrupt Pygame Zero so that it stops animating the screen or even responding to input. Always set the `wait_for_s` or `wait_for_reply_s` options to 0 seconds.

3.4.2 GUI Zero

[GUI Zero](#) is a library for creating Graphical User Interfaces (GUIs) with windows, buttons, sliders, textboxes and so on.

Because GUI Zero and Pygame Zero both provide different approaches for drawing to the screen, they are not usable together.

3.4.3 GPIO Zero

[GPIO Zero](#) is a library for controlling devices connected to the General Purpose Input/Output (GPIO) pins on a Raspberry Pi.

GPIO Zero generally runs in its own thread, meaning that it will usually work very well with Pygame Zero.

Caution: When copying GPIO Zero examples, do not copy the `time.sleep()` function calls or `while True:` loops, as these will stop Pygame Zero animating the screen or responding to input. Use [Clock](#) functions instead to call functions periodically, or the `update()` function to check a value every frame.

3.4.4 Adventurelib

[Adventurelib](#) is a library for creating making text-based games easier to write (and which doesn’t do everything for you!).

Writing text-based games requires a very different set of skills to writing graphical games. Adventurelib is pitched at a slightly more advanced level of Python programmer than Pygame Zero.

Adventurelib cannot currently be combined with Pygame Zero.

Tip: Know of another library that belongs here?

[Open an issue](#) on the issue tracker to let us know!

3.5 Changelog

3.5.1 1.2 - 2018-02-24

- New: *Actors can be rotated* by assigning to `actor.angle`
- New: Actors now have `angle_to()` and `distance_to()` methods.
- New: Actors are no longer subclasses of Rect, though they provide the same methods/properties. However they are now provided with floating point precision.
- New: `tone.play()` function to allow playing musical notes.
- New: `pgzrun.go()` to allow running Pygame Zero from an IDE (see *Running Pygame Zero in IDLE and other IDEs*).
- New: show joystick icon by default
- Examples: add Asteroids example game (thanks to Ian Salmons)
- Examples: add Flappy Bird example game
- Examples: add Tetra example game (thanks to David Bern)
- Docs: Add a logo, fonts and colours to the documentation.
- Docs: Documentation for the *anchor point system for Actors*
- Docs: Add *Migrating from Scratch* documentation
- Fix: `on_mouse_move()` did not correctly handle the `buttons` parameter.
- Fix: Error message when resource not found incorrectly named last extension searched.
- Fix: Drawing wrapped text would cause crashes.
- Fix: `animate()` now replaces animations of the same property, rather than creating two animations which fight.
- Updated ptext to a revision as of 2016-11-17.
- Removed: removed undocumented British English `centrex`, `centrey`, `centre` attribute aliases on ZRect (because they are not Rect-compatible).

3.5.2 1.1 - 2015-08-03

- Added a spell checker that will point out hook or parameter names that have been misspelled when the program starts.
- New ZRect built-in class, API compatible with Rect, but which accepts coordinates with floating point precision.
- Refactor of built-in `keyboard` object to fix attribute case consistency. This also allows querying key state by `keys` constants, eg. `keyboard[keys.LEFT]`.

- Provide much better information when sound files are in an unsupported format.
- `screen.blit()` now accepts an image name string as well as a Surface object, for consistency with Actor.
- Fixed a bug with non-focusable windows and other event bugs when running in a virtualenv on Mac OS X.
- Actor can now be positioned by any of its border points (eg. `topleft`, `midright`) directly in the constructor.
- Added additional example games in the `examples/` directory.

3.5.3 1.0.2 - 2015-06-04

- Fix: ensure compatibility with Python 3.2

3.5.4 1.0.1 - 2015-05-31

This is a bugfix release.

- Fix: Actor is now positioned to the top left of the window if `pos` is unspecified, rather than appearing partially off-screen.
- Fix: repeating clock events can now unschedule/reschedule themselves

Previously a callback that tried to unschedule itself would have had no effect, because after the callback returns it was rescheduled by the clock.

This applies also to `schedule_unique`.

- Fix: runner now correctly displays tracebacks from user code
- New: Eliminate redraws when nothing has changed

Redraws will now happen only if:

- The screen has not yet been drawn
- You have defined an `update()` function
- An input event has been fired
- The clock has dispatched an event

3.5.5 1.0 - 2015-05-29

- New: Added `anchor` parameter to Actor, offering control over where its `pos` attribute refers to. By default it now refers to the center.
- New: Added Ctrl-Q/-Q as a hard-coded keyboard shortcut to exit a game.
- New: `on_mouse_*` and `on_key_*` receive `IntEnum` values as `button` and `key` parameters, respectively. This simplifies debugging and enables usage like:

```
if button is button.LEFT:
```

3.5.6 1.0beta1 - 2015-05-19

Initial public (preview) release.

Tip:



If you're ready to try writing a full game, an event to look out for is [PyWeek](https://pyweek.org/), which happens twice a year at <https://pyweek.org/>.

It's an online game programming challenge: you have a week to write a game in Python, using Pygame Zero or other libraries. Lots of other people will be writing games too, and you can watch their progress and play and rate the finished results after the competition.

4.1 Roadmap

Pygame Zero is an open source project, and as with any such project, the development roadmap is subject to change. This document just lays out some goals for future releases, but there is **no guarantee** that these targets will be hit.

4.1.1 Translations

Pygame Zero is aimed at young users, whose English skills might not be good enough to read the documentation if it isn't in their own language.

Adding translations of the documentation would help to bring Pygame Zero to new users. This is something that needs contributors to help with. My own language skills aren't good enough!

Please see [the translating guide](#) if you think you can help.

4.1.2 Gamepad Support

Github Issue: [#70](#)

SNES-style gamepads are now extremely cheap. For example, they are sold for a few pounds from the [Pi Hut](#), in packs of 2 at [Amazon](#), and even in some Raspberry Pi bundles.

Gamepad support should not be limited to these specific models; rather, we should treat this as a lowest-common-denominator across modern gamepads, as nearly all more modern gamepads have at least as many buttons and axes.

This feature needs to be added in a way that will not **require** a gamepad to play any Pygame Zero game, in order to follow the principle of *Make it accessible*.

4.1.3 Surface juggling

Github Issue: [#71](#)

Pygame experts make lots of use of off-screen surfaces to create interesting effects.

Pygame Zero chose to consider only the screen surface, which we wrap with a richer `Screen` API for drawing, etc.

The problem is that there is no easy path to using additional surfaces - Pygame Zero immediately becomes dead weight as you start to look past that curtain.

We should look to smooth out this path to make Pygame Zero Actors and Screen work better with custom surfaces.

4.1.4 Storage

Github Issue: [#33](#)

It would be useful for users to be able to save and load data.

The obvious application is save games, but saving and loading whole games can be pretty hard to get right. The simpler application would just be saving settings, customisations, high scores, or the highest level reached.

Python of course has APIs for reading and writing files, but this has additional complexity that teachers might not want to teach immediately.

4.2 Principles of Pygame Zero

Please read the following carefully before contributing.

Because Pygame Zero is aimed at beginners we must take extra care to avoid introducing hurdles for programmers who have not yet learned to deal with them.

4.2.1 Make it accessible

The main aim of Pygame Zero is to be accessible to beginner programmers. The design of the API is, of course, influenced by this.

This also applies to things like hardware requirements: Pygame Zero chose originally to support only keyboard and mouse input, in order to be accessible to any user.

4.2.2 Be conservative

Early in the development of Pygame Zero, Richard and I (Daniel) went backwards and forwards over various features. We put them in, tried them and took them out again.

Features should be rejected if they are too experimental, or if they might cause confusion.

This also applies to things like OS support: we disallow filenames that are not likely to be compatible across operating systems.

4.2.3 Just Work

Pygame Zero wraps Pygame almost completely - but we don't expose all the features. We expose only the features that work really well without extra fuss, and hide some of the other features that work less well or need extra steps.

4.2.4 Minimise runtime cost

At the end of the day, Pygame Zero is a games framework and performance is an issue.

Doing expensive checking every frame to catch a potential pitfall is not really acceptable. Instead, we might check at start up time, or check only when an exception is raised to diagnose it and report more information.

4.2.5 Error clearly

When exceptions are thrown by Pygame Zero, they should have clear error messages that explain the problem.

4.2.6 Document well

Like all projects, Pygame Zero needs good documentation. Pull requests are more likely to be accepted if they include the necessary documentation.

Try to avoid complicated sentences and technical terms in the documentation, so that it is more easily readable by inexperienced programmers.

4.2.7 Minimise breaking changes

In educational environments, users don't always have control of the version of a library they use. They don't know how to install or upgrade to the latest version.

It is more important to get the features right first time than in many other projects.

4.3 Contributing to Pygame Zero

The Pygame Zero project is hosted on GitHub:

<https://github.com/lordmauve/pgzero>

4.3.1 Reporting an bug or request

You can report bugs, or request features that you think should be in Pygame Zero, using the [Github issue tracker](#).

Here are some things to bear in mind before you do this:

- It might not just be you! You should check if someone has already reported the issue by searching through the existing issues - both open and closed.
- The developers need to know what version of Pygame Zero you are using, and what operating system you are running (Windows, Mac, Linux etc) and version (Windows 10, Ubuntu 16.04, etc).

4.3.2 How to do a pull request

You can make changes to Pygame Zero by creating a pull request.

It's a good idea to *report an issue* first, so that we can discuss whether your change makes sense.

Github has [help on how to create a pull request](#), but here's the quick version:

1. Make sure you are logged into Github.

2. Go to the [Github page for Pygame Zero](#).
3. Click “Fork” to create your own fork of the repository.
4. Clone this fork to your own computer:

```
git clone git@github.com:yourusername/pgzero.git
```

Remember to change yourusername to your Github username.

5. Create a branch in which to do your changes. Pick a branch name that describes the change you want to make.

```
git checkout -b my-new-branch master
```

6. Make the changes you want.
7. Add the files that you want to commit:

```
git add pgzero
```

8. Commit the files with a clear commit message:

```
git commit -m "Fixed issue #42 by renaming parameters"
```

You can do steps 6 to 8 as many times as you want until you’re happy.

9. Push the commit back to your fork.

```
git push --set-upstream origin my-new-branch
```

10. Go to the Github page for your fork, and click on the “Create pull request” button.

4.3.3 Development installation

It’s possible to create a locally-editable install using pip. From the root directory of the checked out source, run:

```
pip3 install --editable .
```

The installed version will now reflect any local changes you make.

Alternatively, if you don’t want to install it at all, it may be run with:

```
python3 -m pgzero <name of pgzero script>
```

For example:

```
python3 -m pgzero examples/basic/demo1.py
```

4.3.4 How to run tests

The tests can be run with

```
python3 setup.py test
```

4.3.5 Helping to translate the documentation

Pygame Zero's APIs will always be English, but we can bring Pygame Zero to more users around the world if the documentation is available in their language.

If you are fluent in another language, please consider contributing by translating all or part of the documentation.

The documentation is written in [reStructuredText](#), which is a text-based markup language for technical documentation. As much as possible, the existing formatting should be preserved. [reStructuredText](#) isn't too difficult once you get used to it.

Creating a translation is done by creating a separate repository on Github with a copy of the documentation, rewritten (at least in part) into the language you would like to support. One advantage of this is that you can work on translations at your own pace, without having to submit pull requests back to the `pgzero` project itself. Please see the [translation guide](#) on Read The Docs for details.

If this sounds like something you could tackle, here's how you might go about it:

1. First, open an issue on the [pgzero issue tracker](#). You should search for an existing issue covering the translation you want to do, before opening a new one. This will help ensure that you don't do translation work that has already been done by someone else (perhaps you can collaborate instead).
2. Create a new Github repository under your user, called *pgzero-language*, eg. *pgzero-spanish* if you're going to translate into Spanish.
3. Clone the repository to your own computer.
4. Download the Pygame Zero `doc/` directory and commit it in your project. You can do this by extracting them from [repository ZIP file](#). You only need the `doc/` directory from the ZIP file. You can delete the other files.
5. Now, work through the `.rst` files in the docs directory, translating, using your preferred editor. You should commit regularly, and push your commits to Github.
6. Post a link to your repository as a comment in the Github issue you created in step 1. You can do this as soon as you have some progress to show; this will help people collaborate with you on the translation if they are interested.
7. [Set up the documentation to build on Read The Docs](#). Again, post a comment on the Github issue when you have this working.
8. We can then link up the new, translated documentation with the Pygame Zero documentation.

Note that Pygame Zero will have updates, and the documentation will be changed accordingly. Using Git it is possible to see a diff of what changed in the English documentation, so that you can make corresponding changes in the translated documentation.

A

A (*keys attribute*), 19
ALT (*keymods attribute*), 22
AMPERSAND (*keys attribute*), 18
angle_to() (*Actor method*), 35
animate() (*built-in function*), 36
Animation (*built-in class*), 36
ASTERISK (*keys attribute*), 18
AT (*keys attribute*), 19

B

B (*keys attribute*), 19
BACKQUOTE (*keys attribute*), 19
BACKSLASH (*keys attribute*), 19
BACKSPACE (*keys attribute*), 18
blit() (*Screen method*), 26
BREAK (*keys attribute*), 21

C

C (*keys attribute*), 19
CAPS (*keymods attribute*), 22
CAPSLOCK (*keys attribute*), 21
CARET (*keys attribute*), 19
circle() (*Screen.draw method*), 27
CLEAR (*keys attribute*), 18
clear() (*Screen method*), 26
Clock (*built-in class*), 31
COLON (*keys attribute*), 19
COMMA (*keys attribute*), 18
CTRL (*keymods attribute*), 22

D

D (*keys attribute*), 19
DELETE (*keys attribute*), 20
distance_to() (*Actor method*), 35
DOLLAR (*keys attribute*), 18
DOWN (*keys attribute*), 20
draw() (*built-in function*), 15

E

E (*keys attribute*), 19
END (*keys attribute*), 20
EQUALS (*keys attribute*), 19
ESCAPE (*keys attribute*), 18
EURO (*keys attribute*), 21
EXCLAIM (*keys attribute*), 18

F

F (*keys attribute*), 19
F1 (*keys attribute*), 21
F10 (*keys attribute*), 21
F11 (*keys attribute*), 21
F12 (*keys attribute*), 21
F13 (*keys attribute*), 21
F14 (*keys attribute*), 21
F15 (*keys attribute*), 21
F2 (*keys attribute*), 21
F3 (*keys attribute*), 21
F4 (*keys attribute*), 21
F5 (*keys attribute*), 21
F6 (*keys attribute*), 21
F7 (*keys attribute*), 21
F8 (*keys attribute*), 21
F9 (*keys attribute*), 21
fill() (*Screen method*), 26
filled_circle() (*Screen.draw method*), 27
filled_rect() (*Screen.draw method*), 27

G

G (*keys attribute*), 19
get_height() (*Surface method*), 29
get_length() (*Sound method*), 29
get_rect() (*Surface method*), 29
get_size() (*Surface method*), 29
get_width() (*Surface method*), 28
GREATER (*keys attribute*), 19

H

H (*keys attribute*), 19

HASH (*keys attribute*), 18
HELP (*keys attribute*), 21
HOME (*keys attribute*), 20

I

I (*keys attribute*), 19
INSERT (*keys attribute*), 20

J

J (*keys attribute*), 19

K

K (*keys attribute*), 19
K_0 (*keys attribute*), 18
K_1 (*keys attribute*), 18
K_2 (*keys attribute*), 18
K_3 (*keys attribute*), 18
K_4 (*keys attribute*), 19
K_5 (*keys attribute*), 19
K_6 (*keys attribute*), 19
K_7 (*keys attribute*), 19
K_8 (*keys attribute*), 19
K_9 (*keys attribute*), 19
keymods (*built-in class*), 22
keys (*built-in class*), 18
KP0 (*keys attribute*), 20
KP1 (*keys attribute*), 20
KP2 (*keys attribute*), 20
KP3 (*keys attribute*), 20
KP4 (*keys attribute*), 20
KP5 (*keys attribute*), 20
KP6 (*keys attribute*), 20
KP7 (*keys attribute*), 20
KP8 (*keys attribute*), 20
KP9 (*keys attribute*), 20
KP_DIVIDE (*keys attribute*), 20
KP_ENTER (*keys attribute*), 20
KP_EQUALS (*keys attribute*), 20
KP_MINUS (*keys attribute*), 20
KP_MULTIPLY (*keys attribute*), 20
KP_PERIOD (*keys attribute*), 20
KP_PLUS (*keys attribute*), 20

L

L (*keys attribute*), 19
LALT (*keymods attribute*), 22
LALT (*keys attribute*), 21
LAST (*keys attribute*), 22
LCTRL (*keymods attribute*), 22
LCTRL (*keys attribute*), 21
LEFT (*keys attribute*), 20
LEFT (*mouse attribute*), 18
LEFTBRACKET (*keys attribute*), 19

LEFTPAREN (*keys attribute*), 18
LESS (*keys attribute*), 19
line () (*Screen.draw method*), 27
LMETA (*keymods attribute*), 22
LMETA (*keys attribute*), 21
LSHIFT (*keymods attribute*), 22
LSHIFT (*keys attribute*), 21
LSUPER (*keys attribute*), 21

M

M (*keys attribute*), 19
MENU (*keys attribute*), 21
META (*keymods attribute*), 22
MIDDLE (*mouse attribute*), 18
MINUS (*keys attribute*), 18
MODE (*keymods attribute*), 22
MODE (*keys attribute*), 21
mouse (*built-in class*), 18
music.fadeout () (*built-in function*), 30
music.get_volume () (*built-in function*), 30
music.is_playing () (*built-in function*), 30
music.pause () (*built-in function*), 30
music.play () (*built-in function*), 30
music.play_once () (*built-in function*), 30
music.queue () (*built-in function*), 30
music.set_volume () (*built-in function*), 30
music.stop () (*built-in function*), 30
music.unpause () (*built-in function*), 30

N

N (*keys attribute*), 19
NUM (*keymods attribute*), 22
NUMLOCK (*keys attribute*), 21

O

O (*keys attribute*), 19
on_finished (*Animation attribute*), 36
on_key_down () (*built-in function*), 17
on_key_up () (*built-in function*), 17
on_mouse_down () (*built-in function*), 16
on_mouse_move () (*built-in function*), 17
on_mouse_up () (*built-in function*), 17
on_music_end () (*built-in function*), 17

P

P (*keys attribute*), 19
PAGEDOWN (*keys attribute*), 20
PAGEUP (*keys attribute*), 20
PAUSE (*keys attribute*), 18
PERIOD (*keys attribute*), 18
play () (*Sound method*), 29
PLUS (*keys attribute*), 18
POWER (*keys attribute*), 21

PRINT (*keys attribute*), 21

Q

Q (*keys attribute*), 19

QUESTION (*keys attribute*), 19

QUOTE (*keys attribute*), 18

QUOTEDBL (*keys attribute*), 18

R

R (*keys attribute*), 20

RALT (*keymods attribute*), 22

RALT (*keys attribute*), 21

RCTRL (*keymods attribute*), 22

RCTRL (*keys attribute*), 21

rect () (*Screen.draw method*), 27

RETURN (*keys attribute*), 18

RIGHT (*keys attribute*), 20

RIGHT (*mouse attribute*), 18

RIGHTBRACKET (*keys attribute*), 19

RIGHTPAREN (*keys attribute*), 18

RMETA (*keymods attribute*), 22

RMETA (*keys attribute*), 21

RSHIFT (*keymods attribute*), 22

RSHIFT (*keys attribute*), 21

RSUPER (*keys attribute*), 21

running (*Animation attribute*), 36

S

S (*keys attribute*), 20

schedule () (*Clock method*), 31

schedule_interval () (*Clock method*), 31

schedule_unique () (*Clock method*), 31

Screen (*built-in class*), 26

SCROLLOCK (*keys attribute*), 21

SEMICOLON (*keys attribute*), 19

SHIFT (*keymods attribute*), 22

SLASH (*keys attribute*), 18

Sound (*built-in class*), 29

SPACE (*keys attribute*), 18

stop () (*Animation method*), 36

stop () (*Sound method*), 29

Surface (*built-in class*), 28

surface (*Screen attribute*), 26

SYSREQ (*keys attribute*), 21

T

T (*keys attribute*), 20

TAB (*keys attribute*), 18

text () (*Screen.draw method*), 27

textbox () (*Screen.draw method*), 27

tone.create () (*built-in function*), 37

tone.play () (*built-in function*), 36

U

U (*keys attribute*), 20

UNDERSCORE (*keys attribute*), 19

unschedule () (*Clock method*), 32

UP (*keys attribute*), 20

update () (*built-in function*), 16

V

V (*keys attribute*), 20

W

W (*keys attribute*), 20

WHEEL_DOWN (*mouse attribute*), 18

WHEEL_UP (*mouse attribute*), 18

X

X (*keys attribute*), 20

Y

Y (*keys attribute*), 20

Z

Z (*keys attribute*), 20